

Clarens

Clarens / Canton of Vaud / Switzerland

Ballast bonding



Contracting authority

Swiss Federal Railways
Avenue de la Gare 43
1003 Lausanne
Mrs. Nadya Hannane

Application date

June 2021

Key elements of the project:

Length of the application
597 m¹

Width of the application
50 cm

Depth of the application
50 cm - 55 cm

Total quantity applied
2583 Litres

Working hours
9 hours



Description of the project

As part of the project in Clarens, various renovation works were carried out as well as the new construction of the drainage system.

In order to work on the track and install the drainage, the ballast was bonded to the adjacent track.

This allowed the secondary track to remain in service on the busy line and the other track to be renovated safely. And the drainage has been installed.

